



DAV PUBLIC SCHOOL, LAKHISARAI

NH-80, BARAHIYA ROAD, LAKHISARAI-811311

(Managed By: DAV College Managing Committee, New Delh-110055)

Contact: 9905682671 e-Mail-davki@yahoo.in

Ref. no: DAV/Lakhisarai/2025/507

Date: 01/11/2025

TENDER NOTICE FOR THE FOLLOWING WORK AT DAV PUBLIC SCHOOL, LAKHISARAI – 811 311

Tender in closed and sealed envelop is invited from eligible firm for the following:


- 1) Fixing New Door at New Toilet
- 2) Removal of Broken Glass and Installation of New Fiber Glass
- 3) Installation of Two Water Tanks of 5000L each
- 4) Construction of Shed Over Stage
- 5) Glass Door Installation in Reception Area
- 6) Kota Stone Laying in 10 Class Rooms
- 7) Construction of Drain Covers

Eligibility & Other Information:


- 1) The bidders should be an Indian Firm engaged in civil work and Registered as per existing norms from Government Department.
- 2) They should have minimum three years of experience in the field and worked with Govt. Depts/PSUs/MNCs/etc.
- 3) They should not have been blacklisted by the Departments/Ministries of the Govt. of India Declaration to this effect is to be submitted.
- 4) For bidding, the firms are required to submit the following self-attested and duly rubber stamped (on each page) photocopies of the following documents relating to their printing press/firm:
 - a) Registration Certificate as per existing norms from Government Department;
 - b) Copy of GST Registration Certificates;
 - c) Copy of latest GST return;
 - d) Copy of PAN Card,
 - e) Declaration regarding blacklisting
- 5) The rate should be quoted in Indian Rupees (in both words and figures) only.
- 6) Offered rates are negotiable.
- 7) Standard quality materials be used.
- 8) The work must be completed withing 02 month from the date of allotment of the said work.
- 9) Tender in a **CLOSED & SEALED ENVELOPE** should be addressed to ---
THE PRINCIPAL, DAV PUBLIC SCHOL, NH-80, BARAHIYA ROAD, LAKHISARAI – 811 311 And must reach on or before 10/11/2025; 17:00 HRS
Note: Tender in a closed and sealed envelope must be sent through Registered Post/Courier or can be submitted by hand.
- 10) In the event of failure on the part of work by the Bidder/Firm, the rest work may get completed from another firm and the previously engaged bidder/firm will have to reimburse the extra expenditure incurred thereafter.
- 11) Payment against Bill/Invoice shall be released only after completion of the work to the satisfaction of the architect & competent committee. No interest will be payable on the delayed payments. Payment will be made directly to the firm through Multi-city cheque only. No request for other mode of payment will be entertained.

Work is divided in Two parts and payment of each part will be made separately on completion of work. No advance payment will be made in any case. However, part payment can be done on satisfaction of Architect.

- 12) The Tenderer will be bound by the details furnished by him/her while submitting the tender or at subsequent stage. In case, any of such documents furnished by him/her found to be fictitious at any stage, it would be deemed to be a breach of terms of contract making him/her liable for legal action besides termination of the contract.
- 13) No charges such as Octroi, packing, forwarding, freight insurance, loading and unloading, entry tax, demo, etc. will be allowed. All these are to be borne by the bidder only.
- 14) The Tenderer is not bound to accept the lowest bidder rather he/she is free to accept the bid on the basis of experience and technical viability.
- 15) This office has right to amend any T&C Listed in the documents as per the changes notified by the Govt. and has right to add or delete any Para for quality management of the work.
- 14) The details of the work to be done is available in the school's website i.e www.davlakhisarai.com.
- 15) Technical bid should be submitted on or before 05/11/2025 through email davlki@yahoo.in.
- 16) The financial bid will be opened on 17/11/2025 at Asstt Regional Office, DAV Public Schools, Bihar Zone-D, C/o BR DAV Public School, Refinery Township, (IOCL), Begusarai at 11:30 a.m.
- 17) The defect and liability period shall be for 12 months. 10% of final approved bill amount of the contractors shall be retained as retention money upto 12 months from the date of handing over.


Principal
Principal
DAV Public School
NH-80, Lakhisarai-811311
Affiliation No.- 330232


Manager
Manager
DAV PUBLIC SCHOOL
Barahiya Road, Lakhisarai
Bihar-811311
Affiliation No.-330232


Asstt Regional Officer
Asstt. Regional Officer
DAV Public School
Bihar Zone - D,
Begusarai

BOQ

1. ABSTRACT OF COST FOR FIXING NEW DOOR AT NEW TOILET AT DAV PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no

Date

Serial	SoR	Particulars	AREA	QUANTITY	Unit	Amount
		MAIN DOOR SIZE FOR NEW TOILET (4' X 7')	28	1	SQFT	28
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		DOOR CHANGE (4' X 7')				
1		preparation of frame and opening and also finishing after door installation	lumsun			
2		Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	2.6		sqm	
3		Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	5.2		sqm	
			TOTAL			

SAY TOTAL -/-

ONLY

Note :

Rates are inclusive of G.S.T.

2. ABSTRACT OF COST FOR REMOVAL OF BROKEN GLASS AND INSTALLATION OF NEW FRIBRE GLASS ONES IN WINDOWS OF BUILDINGS THROUGHOUT CAMPUS OF AT - D A V PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no

Date

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		Based on calculation throughout campus which includes classrooms, administration areas, toilets etc <u>approximate area count of 1' x 1' glass panes required</u>	4,000.0		SQFT	
1		Providing & fixing Fibre reinforced glass panes with putty and glazing clips in doors, windows, clerestory windows all complete with. 5.00 mm thick glass . <u>(cutting and fixing of 1' x 1' glass pane)</u>	371.7		sqm	0
2		Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 meters lead. Of area 3 sqm and below, <u>(including cutting, carriage, fixing using silicon clips if required and labour cost for every fibre glass pane of average size 1'x1')</u>	4,000.0		each	0
			GRAND TOTAL			
			SAY, TOTAL COST- Rs.-/-			
			(.....)			

NOTE-

1. rates are inclusive of G.S.T

2. average size of fibre glass panes is taken averagely as 1'x1'

3. approximately 4000 such panes needed around campus

3. Payment for the work should be done on the basis of final count/area of work executed.

3. ABSTRACT OF COST FOR INSTALLATION OF 2 WATER TANKS OF 5000L EACH AT D.A.V PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no

Date.....

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
WATER TANK						
1		Providing and placing on terrace (at all floor levels) polyethylene water storage tank, ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	5,000.0		per litre	
		cost of one tank				
		(water tanks of capacity 5000 lts and well approved brand)	2.0		each	
2		Brass full way valve with C.I. wheel (screwed end) 25 mm dia	4.0		each	
3		Providing and fixing Polyethelene-Aluminium-Polyethelene (PE-ALPE) Composite Pressure Pipes conforming to IS - 15450, including all special fittings of composite materials 2025 (25 mm OD) pipe	146.0		metre	
TOTAL						

SAY TOTAL/-

Note: rates are inclusive of GST.

4. ABSTRACT OF COST FOR CONSTRUCTION OF SHED OVER STAGE AT -DAV PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no

Date

		STAGE SIZE (51' X 31')	1581.0		sqft	
		SHED	1581.0		sqft	
1		Providing PCC (1:2:4) with graded Stone chips of 20 mm nominal size excluding the cost of centring and shuttering all works in Foundation all complete	3.0		Cu m	
2		iron pole (4" dia) (16' high)(6 nos.)(32 kg each) (2kg/ft)	192		kg	
3		truss (51' long) (3 pc each almost weighing 255 kg) (5kg/ft)	765		kg	
4		purlins (31' long) (7 pc each wieghing almost 46.5 kg each) (1.5kg/ft)	325.5		kg	
5		PVC Shed	146.0		Sq m	
6		gutter and channel along with pipe for rain water collection (providing, cutting and installing included)	22.0		m	
7		Bolts And Fastners (G.I wire, nut bolt, s-cup)		lumsum		
TOTAL						
SAY TOTAL COST - Rs/-						

Note:

Rates are inclusive of GST

5. ABSTRACT OF COST FOR GLASS DOOR INSTALLATION IN RECEPTION AREA AT D.A.V PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no - DAV-HA-

Date -

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		glass door - 1x(9'10" x 12')	118			
		glass door - 2x(10'10" x 12')	130			
		glass door - 1x(11'2" x 12')	134			
		total area	382			

		total no. of doors	4			
1		toughened glass panels to be cut and finished as per required size and depending on no. of lpanels (inclusive of holes and cutting)	35.5		sqm	
2		handle bars	8.0		EACH	
3		Floor grouts	4.0		EACH	
4		brackets	4.0		EACH	
5		transportation and labour	4.0		EACH	
			TOTAL			

SAY TOTAL -/-

..... ONLY

Note :

Rates are inclusive of G.S.T.

6. ABSTRACT OF COST FOR CONSTRUCTION OF DRAIN COVERS AT - D A V PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no :

Date :

		SIZE OF DRAIN COVERS (2'X2')	4	SQFT		
		NO. OF COVERS	100	UNIT		
		TOTAL AREA OF COVERS	400	SQFT		
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
1		Centring and shuttering including strutting, propping etc. and removal of form				
		Foundations, footings, bases of columns etc. for mass concrete.	150.0		Sq m	
2		Providing and laying upto floor five level reinforced cementconcrete in kerbs, steps and the like excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4(1cement:2 coarse sand:4 graded stone aggregate 20mm nominal size).	6.0		Cu m	
3		Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.				
		Thermo-Mechanically Treated bars TMTC-500-8mm dia.	250.0		kg	
4		Miscellaneous charges, like labour and carriage	lumsun			
			Total			
SAY, TOTAL COST- Rs/-						
(.....)						

Note: Rates are inclusive of G.S.T

7. ABSTRACT OF COST FOR KOTA STONE LAYING IN 10 CLASSROOMS AT D.A.V PUBLIC SCHOOL, LAKHISARAI, BIHAR

Ref no

Date

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		AREA OF 1 CLASSROOM (25' X 20') EACH	500		SQFT	
		TOTAL NO. OF CLASROOMS	10			
		TOTAL KOTA AREA	5,000.0			
1		Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete . Base with 1:1:1 (1 lime : 1 surkhi: 1 coarse sand) / 1:4 (1 cement: 4 coarse sand)	464.7			
		AREA FOR SKIRTING (4")	28.00			
		total area	492.68		Sq M	
			TOTAL			
SAY TOTAL -/-						
.....						

Note:

Rates are inclusive of GST

Payment to be processed as per work done on site

The following proforma of the check list need to be filled by the Tenderer Mandatorily

1) Name and complete address of the Firm/Company

[illegible]

- 3) **Registration No. & Date :** _____
- 4) **Certificate from Govt. Dept. (Yes/No) :** _____
- 5) **GST Registration NO:** _____
- 6) **Proof of last GST return (Yes/No):** _____
- 7) **PAN No:** _____
- 8) **Proof of three years' work experience with Govt. Dept/PSU's having similar kind of work (Yes/No):** _____
- 9) **Declaration for not blacklisted by the Govt. Dept. PSU's etc (Yes/No):**

- 10) **Rate of different works including GST attached. (Yes/No):**

- 11) **Rate of different works excluding GST attached. (Yes/No):** _____

I/We certify that the information furnished above is true and correct. In case, any of such information/documents furnished by me/us are found to be fictitious, it would be deemed to be a breach of T&C and liable for legal action.

Date: _____

Name & Designation of Authorised Signatory & Seal of the firm